


## **Case Dimensions (in inches/cm.)**



For answers to your Monogram,®

- GE Profile Performance Series,™
- GE Profile™ or GE appliance questions, call
- GE Answer Center® service, 800.626.2000.




Total volume and shelf area are calculated by the Association of Home Appliance Manufacturers' standards.








### **Rough-In Dimensions (in inches)**



"The rough-in dimension of 70-1/4" is minimum and is measured from the finished floor to top of opening (or the underside of the overhead cabinets). For Models with Trim Kit: If trameless style cabinets are planned for above the retrigerator, you may need to consider adding a maximum of 14" (70-1/2") to height of opening to allow additional clearance between cabinet doors and top of refrigerator trim when cabinet doors are in open position.



#### Standard, New Construction and Replacement Installation

#### Installation Tips to Maximize the Built-In Look

- All wall/floor moulding should be removed prior to installation.
- Water recess on rear wall recommended to prevent water line damage. 48" minimum length 1/4" diameter water line tubing recommended.
- When possible, recess both water line and electrical outlet. (See local codes)
- Front and rear leveling legs are adjustable for the "Built-In" look. (See owner's manual)
- If optional collar trim kit is to be used or anticipated, see collar trim installation on next page for different rough-in dimensions.

IMPORTANT: Before finalizing for your GE Profile Performance™ and GE Profile™ CustomStyle™ Refrigerator, please NOTE:

- A minimum of 36" is required for Refrigerator installation.
- Be sure to allow for 1/2" or 3/4" side panels in addition to the 36" minimum.

### **Door Panel Dimensions (in inches)**

Order your own custom wood panels to match cabinetry or other decor.

	Fresh Food Panels	Freezer Panel With Dispense	r	Freezer Panel Without Dispenser	Weight Limits*
21 cu. ft.	<b>G</b> -65-3/16" <b>H</b> -20-1/16"	<b>C</b> -18-3/4" <b>D</b> -14-5/16"	<b>E</b> -32-3/8" <b>F</b> -14-5/16"		Fresh Food = 38 lbs. Freezer = 28 lbs.
24 cu. ft.	<b>G</b> -67-1/8" <b>H</b> -19-5/16"	<b>C</b> -18-13/16" <b>D</b> -14-1/2"	<b>E</b> -34-5/16" <b>F</b> -14-1/2"	<b>A</b> -67-1/8" <b>B</b> -14-1/2"	Fresh Food = 35 lbs. Freezer = 25 lbs.

Panels up to 1/4" thick will fit door frame with no special preparation. Add filler behind material thinner than 1/4" for proper fit.

\*Total weight of panels (i.e. both freezer panels)

**Note:** Panels up to 3/4" will require special routing area around handles. Dimensions may vary depending on depth of panel.

#### Detail C



(Fresh Food panel shown) Notch required at top corner as noted.




For answers to your Monogram,  $\!\!^{\scriptscriptstyle{(\!0\!)}}$ 

GE Profile Performance Series,™

GE Profile™ or GE appliance questions, call

GE Answer Center® service, 800.626.2000.



\*For 24 cu. ft. models only




Total volume and shelf area are calculated by the Association of Home Appliance Manufacturers'









### **Collar Trim Installation**




\*The rough-in dimension of 70-1/4" is minimum and is measured from the finished floor to top of opening (or the underside of the overhead cabinets). For Models with Trim Kit: If frameless style cabinets are planned for above the refrigerator, you may need to consider adding a maximum of 1/4" (70-1/2") to height of opening to allow additional clearance between cabinet doors and top of refrigerator trim when cabinet doors are in open position.



**Specification Revised 5/00** 





## Typical Installation

Overhead

Case

Cabinet

Shaded areas represent front surfaces of side panels and overhead cabinet or soffit that contacts trim.

Top

Trim

Cabinet

Door

#### **Collar Trim Installation**

An enclosure is **required** to match up to the trim, see Typical Installation. To obtain the most integrated look, the cabinet or soffit above the refrigerator should extend out to the same depth as the side panels. The refrigerator opening must have minimum dimensions of 70-1/4" high x 36-1/8" wide x 24-1/2"\* deep as shown at right. If there is an overhead cabinet, allow 1" for cabinet door clearance with the top trim piece so the cabinet doors can be opened without hitting the top trim. If 1/2" side panels are used, then side trim and panel will be even. If 3/4" side panels are used, then some of the side panel will extend beyond the trim and must be finished.

\*24-1/2" Depth applies to the refrigerator opening, not the actual cabinet depth.

IMPORTANT: Before finalizing for your GE Profile Performance™ and GE Profile™ CustomStyle™ Refrigerator, please NOTE:


- A minimum of 36-1/8" is required for Refrigerator installation.
- Be sure to allow for 1/2" or 3/4" side panels in addition to the 36-1/8" minimum.

For answers to your Monogram,®
GE Profile Performance Series,™
GE Profile™ or GE appliance questions, call
GE Answer Center® service, 800,626,2000.









### **Features and Benefits**

- 23.7 cu ft Capacity (Fresh Food 14.48 cu ft / Freezer 9.25 cu ft)
- LightTouch! Dispenser Delivers Chilled Water, Cubed and Crushed Ice through the Door
- Freshness Center™ (1 Adjustable Humidity Crisper, 1 Convertible Meat Keeper with Cold Control and 1 Adjustable Humidity Snack Pan) with Spill-Proof Cover
- 3 Adjustable Glass Fresh Food Cabinet Shelves (2 Slide Out, Spill Proof)
- Quick Space<sup>™</sup> Shelf
- ShelfSaver<sup>™</sup>
- 4 ClearLook™ Modular Fresh Food Door Shelves (2 Adjustable with Gallon Storage)
- Beverage Rack
- Dairy Compartment with Glass Butter Dish
- Egg Bin
- 3 Cantilevered Freezer Shelves (2 Adjustable)
- 1 Wire Everwhite, Slide Out Freezer Basket
- 1 Sliding Wire Everwhite Freezer Storage bin
- 4 Freezer Door Shelves (2 Adjustable)
- Quiet Package II
- Color-Matched Full-Length Door Handles
- Model TPX24BRDWW—White on White
- Model TPX24BRDBB—Black on Black
- Model TPX24BRDAA—Almond on Almond