


GE Appliances

AZ58H07E – GE Zoneline® Premium Series Heat Pump Unit

Wall Case Dimensions




RAB71 Wall Sleeve

Heavy-gauge galvanized steel, with insulation. A -42", B -13-3/4", C -16"

RAB77 Wall Sleeve

Molded SMC fiberglass-reinforced polyester compound. A - 42-1/8". B - 13-7/8". C - 16-1/4

Maximum Cord Extension (in inches)



Wall Opening Dimensions

Add 1/4" to A and C dimensions for all cut-out size. RAB71 16-1/4" Min. H x 42-1/4" Min. W RAB71 available in 16", 24", 28" and 31" depths RAB77 16-1/2" Min. H x 42-3/8" Min. W

265 Volt Sub-Base Connected Units Min. Circuit **Power** Electric **Electric Protection** Sub-Base Connection Kit **Heater Watts Heat Amps** (Amps) RAK204E15 RAK5172 2.550 10.3 15 RAK5202 13.7 20 RAK204E20 3,450 RAK204E30 RAK5302 5.000 19.6 30

Electrical Wiring

All wiring, including installation of receptacle, must be made in accordance with local electrical codes and regulations.

Note: Aluminum wiring may pose special problems – consult a qualified electrician.

Grille Options

Stamped Aluminum Grille – RAG60

Exterior Architectural Louvers Durable Polycarbonate:

RAG61 or RAG64 (Brita) — RAG63 or RAG66 (Bittor)

RAG61 or RAG64 (Beige) RAG63 or RAG66 (Bittersweet)
RAG62 or RAG65 (Maple) RAG67 (Extruded Aluminum)

Retrofit Kits:

RAK901L – Wall Case Insulation for use with heat pumps. RAK40 – Deflector Kit to adapt chassis for use with existing exterior architectural louvered grilles.

Electrical Connection

230/208 volt units may be plugged into a receptacle. 265 volt units are provided with a junction box and require direct connection. (NEC Requires 265V Direct Connection) See Architects and Engineers Design Data Manual for electrical connection information including use of sub-base for direct connected units. Installation must comply with local electrical codes and regulations.


Power Connection kits required on all Zoneline chassis.

For answers to your Monogram,® GE Profile™ or GE® appliance questions, visit our website at ge.com or call GE Answer Center® service, 800.626.2000.



GE Appliances

AZ58H07E – GE Zoneline® Premium Series Heat Pump Unit



Features and Benefits

- 7100 BTUH (Cooling)
- 13.0 E.E.R.
- 1.7 Dehumidification (pts/hr)
- 6400 BTUH (Reverse Cycle Heat)
- 240/220 CFM Indoor Fan (High/Low)
- 50/40 Vent CFM
- Electronic 7-Step Temperature Limiting To Prevent Overcooling or Overheating of Room
- Heat Sentinel
- Reverse Cycle Defrost By Monitoring Operating Conditions
- 30 Sound Transmission Class (STC)
- High Featured Microcomputer Tactile Touch Pad Controls with LED
- Model AZ58H07EAC Warm grey beige (Corrosion Treated)
- Model AZ58H07EAD Warm grey beige (Internal Condensate Removal)